BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38011/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/05/2020-21, Date: 27-07-2020

Name of Work:Desilting of drains in Devinagara Lottegollahalli and surrounding area in ward no 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	1062.72	Removing and refixing stone slabs of drains and pointing in CM 1:3 cost of all materials, labour, HOM of machineries, curing etc., complete with all leads and lifts as per specifications.	sqm	96.0	Rupees Ninety Six Only
2	262.4	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2m and an average lift upto 1.5m excavated surface levelled and sides neatl;y dressed, the disposed earth to be levelled neatlyu after breaking of clods complete as per specifications.	cum	119.0	Rupees One Hundred Nineteen Only
3	118.08	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications.	Sqm	1814.4	Rupees One Thousand Eight Hundred Fourteen and Forty Paise Only
4	223.04	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	84.0	Rupees Eighty Four Only

Signature of the Contractor

29/09

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/09